



- GENERAL NOTES

1. FIXTURE TYPES Q AND R SHALL BE PROVIDED WITH FULL RANGE DIMMING BALLASTS AND SHALL BE CONTROLLED BY BOTH THE OCCUPANCY SENSORS IN THE SPACE THEY ARE IN AS WELL AS DAYLIGHT SENSORS IN THESE SPACES. THE LAYOUT FOR THE DAYLIGHT SENSORS IS STILL IN DEVELOPMENT. PRICE SHALL BE DETERMINED BASED ON MANUFACTURER'S RECOMMENDATION. PREFERRED MANUFACTURER IS LUTRON.
- NUMBERED NOTES

①

FIXTURES IN THIS LOCATION SHALL BE MOUNTED TO THE TOP OF THE LIGHT SHELF IN THIS LOCATION.

②

THIS FIXTURE SHALL BE AIMED SOUTH INTO THE LARGE LIGHT SAIL OVER THE OPEN OFFICE AREA.

③

THIS FIXTURE SHALL BE AIMED SOUTH INTO THE SMALL LIGHT SAIL OVER THE CORRIDOR ON THE NORTH SIDE OF THE OPEN OFFICE AREA.

④

FIXTURES IN THIS AREA SHALL BE MOUNTED TO THE SECOND FLOOR SLAB AND AIMED DOWN.

⑤

SEE DRAWING E-201 FOR CONTINUATION OF THIS CIRCUIT.

⑥

TASK LIGHTS SHALL BE PROVIDED WITH INTEGRAL SWITCH AND SHALL BE CORD AND PLUG CONNECTED FOR POWER. TASK LIGHTS WILL BE PROCURED AND INSTALLED UNDER A SEPARATE CONTRACT FOR FURNITURE.

The Design Alliance

ARCHITECTS

Suite 2400  
H. W. Oliver Building  
535 Smithfield Street  
Pittsburgh, PA 15222

Tel: (412) 261-0660  
Fax: (412) 261-7071



CJL ENGINEERING

Westpointe Corporate Center One  
1550 Coraopolis Heights Road, Suite 340  
Moon Township, PA 15108  
ph:(412)262-1220 fax:(412)262-2972  
CJL Project #06-106

CONSULTANT

Center for Sustainable Landscapes

for:

Phipps Conservatory and Botanical Gardens

One Schenley Park Drive, Pittsburgh, PA 15213

Date: \_\_\_\_\_

Drawn By: GMF

Checked By: KJR

Approved By: RAJ

File Label: \_\_\_\_\_

Schematic Design Phase: ☐

Design Development Phase: ☐

Construction Documentation Phase: ☒

Progress Drawing: ☒

Released for Bid: ☐

Released for Construction: ☐

Record Drawing: ☐

Revision Schedule		
No.	Date	Description

CSL BUILDING  
FIRST FLOOR  
LIGHTING

E200

Issued for: Pre-Bid; October 02, 2009