

**GENERAL NOTES**

1. FIXTURE TYPES Q AND R SHALL BE PROVIDED WITH FULL RANGE DIMMING BALLASTS AND SHALL BE CONTROLLED BY BOTH THE OCCUPANCY SENSORS IN THE SPACE THEY ARE IN AS WELL AS DAYLIGHT SENSORS IN THESE SPACES. THE LAYOUT FOR THE DAYLIGHT SENSORS IS STILL IN DEVELOPMENT. PRICE SHALL BE DETERMINED BASED ON MANUFACTURER'S RECOMMENDATION. PREFERRED MANUFACTURER IS LUTRON.

**NUMBERED NOTES**

- ① FIXTURES IN THIS LOCATION SHALL BE MOUNTED TO THE TOP OF THE LIGHT SHELF IN THIS LOCATION.
- ② THIS FIXTURE SHALL BE AIMED SOUTH INTO THE LARGE LIGHT SAIL OVER THE OPEN OFFICE AREA.
- ③ THIS FIXTURE SHALL BE AIMED SOUTH INTO THE SMALL LIGHT SAIL OVER THE CORRIDOR ON THE NORTH SIDE OF THE OPEN OFFICE AREA.
- ④ FIXTURES IN THIS AREA SHALL BE MOUNTED TO THE SECOND FLOOR SLAB AND AIMED DOWN.
- ⑤ SEE DRAWING E-201 FOR CONTINUATION OF THIS CIRCUIT.
- ⑥ TASK LIGHTS SHALL BE PROVIDED WITH INTEGRAL SWITCH AND SHALL BE CORD AND PLUG CONNECTED FOR POWER. TASK LIGHTS WILL BE PROCURED AND INSTALLED UNDER A SEPARATE CONTRACT FOR FURNITURE.

**The Design Alliance**

ARCHITECTS

Suite 2400  
H. W. Oliver Building  
535 Smithfield Street  
Pittsburgh, PA 15222

Tel: (412) 261-0660  
Fax: (412) 261-7071



**CJL ENGINEERING**  
Westpoinate Corporate Center One  
1550 Coraopolis Heights Road, Suite 340  
Moon Township, PA 15108  
ph:(412)262-1220 fax:(412)262-2972  
CJL Project #06-186

CONSULTANT

**Center for Sustainable Landscapes**  
for:  
Phipps Conservatory and Botanical Gardens

Date:  
Drawn By: GMF  
Checked By: KJR  
Approved By: RAJ

File Label:  
Schematic Design Phase:   
Design Development Phase:   
Construction Documentation Phase:

Progress Drawing:  
Released for Bid:   
Released for Construction:   
Record Drawing:


No.	Date	Description

**CSL BUILDING FIRST FLOOR LIGHTING**

E200

PROJECT NUMBER: 07036.01

© 2008 THE DESIGN ALLIANCE ARCHITECTS



1 FLOOR PLAN - LIGHTING - CSL BUILDING - FIRST FLOOR  
E200 1/8" = 1'-0"

Issued for: Pre-Bid; October 02, 2009