



- GENERAL NOTES
1. FIXTURE TYPES Q AND R SHALL BE PROVIDED WITH FULL RANGE DIMMING BALLASTS AND SHALL BE CONTROLLED BY BOTH THE OCCUPANCY SENSORS IN THE SPACE THEY ARE IN AS WELL AS DAYLIGHT SENSORS IN THESE SPACES. THE LAYOUT FOR THE DAYLIGHT SENSORS IS STILL IN DEVELOPMENT. PRICE SHALL BE DETERMINED BASED ON MANUFACTURER'S RECOMMENDATION. PREFERRED MANUFACTURER IS LUTRON.
- NUMBERED NOTES
- ①

FIXTURES IN THIS LOCATION SHALL BE MOUNTED TO THE TOP OF THE LIGHT SHELF IN THIS LOCATION.
- ②

THIS FIXTURE SHALL BE AIMED SOUTH INTO THE LARGE LIGHT SAIL OVER THE OPEN OFFICE AREA.
- ③

THIS FIXTURE SHALL BE AIMED SOUTH INTO THE SMALL LIGHT SAIL OVER THE CORRIDOR ON THE NORTH SIDE OF THE OPEN OFFICE AREA.
- ④

FIXTURES IN THIS AREA SHALL BE MOUNTED TO THE SECOND FLOOR SLAB AND AIMED DOWN.
- ⑤

SEE DRAWING E-201 FOR CONTINUATION OF THIS CIRCUIT.
- ⑥

TASK LIGHTS SHALL BE PROVIDED WITH INTEGRAL SWITCH AND SHALL BE CORD AND PLUG CONNECTED FOR POWER. TASK LIGHTS WILL BE PROCURED AND INSTALLED UNDER A SEPARATE CONTRACT FOR FURNITURE.

The Design Alliance

ARCHITECTS

Suite 2400
H. W. Oliver Building
535 Smithfield Street
Pittsburgh, PA 15222

Tel: (412) 261-0660
Fax: (412) 261-7071

CJL ENGINEERING

Westpointe Corporate Center One
1550 Coraopolis Heights Road, Suite 340
Moon Township, PA 15108
ph:(412)262-1220 fax:(412)262-2972
CJL Project #06-106

CONSULTANT

SEALS

Center for Sustainable Landscapes

for:
Phipps Conservatory and Botanical Gardens

One Schenley Park Drive,
Pittsburgh, PA 15213

Date: _____

Drawn By: GMF

Checked By: KJR

Approved By: RAJ

File Label: _____

Schematic Design Phase: ☐

Design Development Phase: ☐

Construction Documentation Phase: ☒

Progress Drawing: ☒

Released for Bid: ☐

Released for Construction: ☐

Record Drawing: ☐

Revision Schedule		
No.	Date	Description

CSL BUILDING FIRST FLOOR LIGHTING

E200

PROJECT NUMBER: 07036.01

© 2008 THE DESIGN ALLIANCE ARCHITECTS

Issued for: Pre-Bid; October 02, 2009

1 FLOOR PLAN - LIGHTING - CSL BUILDING - FIRST FLOOR
E200 1/8" = 1'-0"